



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

CLIENT	Nash & Smash — Dundalk
PROJECT ADDRESS	1145 Merritt Blvd, Dundalk, MD 21222
CONTRACTOR	Design Kitchen and Bath
SCOPE TYPE	Full Restaurant Tenant Improvement — New Build Out
TOTAL AREA	2,000 Square Feet
DATE	May 2026

1. PROJECT OVERVIEW

Design Kitchen and Bath is pleased to submit this proposal for the full tenant improvement build-out of Nash & Smash — Dundalk, located at 1145 Merritt Blvd, Dundalk, MD 21222. This scope covers all labor and materials required to convert the existing 2,000 SF shell space into a fully operational restaurant, including all architectural, mechanical, electrical, plumbing, and finish work as outlined below.

2. SCOPE OF WORK

2.1 Site Preparation

- Protection of existing structural columns to remain (typ.)
- Site cleanup, debris removal, and dumpster service throughout construction
- Coordinate all trades prior to construction to ensure proper sequencing of all work
- Verify all existing conditions prior to construction; notify owner of any discrepancies

2.2 Framing & Rough Carpentry

- New metal stud framing (33 mil min.) for all new partition walls per approved layout
- Full-height stud partitions at kitchen/dining separation, restrooms, and storage areas
- Wood blocking installed at all locations requiring wall-mounted equipment, casework, grab bars, and accessories
- All framing coordinated with mechanical, electrical, and plumbing rough-in prior to closing walls



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

2.3 Drywall & Interior Finishes

- Install 5/8" Type X drywall on all new partitions; tape, float, and paint-ready finish
- Dining area (Zone 101): Ceiling per plan; FRP wall board panel at kitchen areas; painted GYP.BD. elsewhere
- Restrooms (Zone 102): Ceiling per plan; tile cove base per plan; painted high gloss above +4'-0"
- Kitchen / Prep (Zone 103): Floor per plan; ceiling per plan; FRP wall board throughout kitchen
- All suspended ceilings in food prep areas and restrooms: commercial grade Genesis PVC ceiling panels — smooth, nonabsorbent, and washable per code

2.4 Flooring

- Dining area (Zone 101): Floor tile per plan with tile base
- Restrooms (Zone 102): Floor tile per plan with tile cove base
- Kitchen / Prep (Zone 103): Floor tile per plan with tile base
- All floor sinks and waste receptacles located under case work, placed at leading edge of equipment for accessibility and cleaning

2.5 Doors, Frames & Hardware

- Supply and install all new interior hollow metal or wood doors and frames per layout
- ADA-compliant accessible door hardware at all restroom entries
- Walk-in box doors and hardware furnished and installed by walk-in manufacturer per their shop drawings
- All exit doors and egress hardware per IBC and Baltimore County fire code requirements

2.6 Walk-In Cooler / Freezer

- Furnish and install walk-in cooler and walk-in freezer units per layout
- Owner/tenant to select and confirm walk-in manufacturer; contractor to coordinate shop drawings and final installation
- Foam plastic insulated panels meeting Class B per IBC Table 803.12; flame spread index 25 or less; max 10" thickness
- Self-ignition temperature not less than 600°F (316°C); smoke-developed index not more than 450



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

- Panel base metal not less than 0.0160" aluminum or corrosion-resistant coated steel
- All walk-in casters provided; all sewage drain lines boxed and cabinetry sealed to prevent overflow

2.7 Kitchen Hood & Exhaust System

- Furnish and install 18' Type I commercial kitchen exhaust hood (Econ Air or approved equal) with manual pull station, control panel, and hood supports
- Fabricate and install 18"x18" welded grease duct from hood to roof penetration; sealed and insulated per NFPA 96 and SMACNA
- Upblast exhaust fan at roof; duct extension not less than 18" above roofline per code
- Grease duct cleanout access panels provided at required intervals; horizontal duct at 2% slope toward grease drip cup
- Kitchen hood solenoid valves and automatic gas shut-off tied to fire suppression system; all under-hood cooking equipment (electric and gas) to shut off upon hood activation
- Duct smoke detectors installed on HVAC units serving kitchen; coordinated with fire alarm system

2.8 HVAC / Mechanical

- HVAC rooftop units to be provided by Landlord; contractor scope limited to ductwork, diffusers, and grilles
- Furnish and install all new supply/return ductwork, diffusers, and grilles per mechanical plan for 2,000 SF
- All HVAC diffusers and grilles balanced to design CFM and positioned per reflected ceiling plan
- New supply duct fabricated from galvanized steel per SMACNA; flex duct supported every 4 feet; all duct seams sealed with approved mastic or mastic-plus-fabric tape
- Foil-faced low-density duct insulation on all supply ductwork in unconditioned spaces
- Duct smoke detectors on all HVAC systems handling 2,000 CFM or more; wired to shut down units on activation
- All HVAC diffusers and grilles coordinated with electrical lighting layout; contractor to notify owner of any conflicts

2.9 Plumbing

- Complete new plumbing rough-in and finish for all fixtures per plans: 3-compartment sink, mop sink, 1-compartment sink, hand sinks (2), floor sinks



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

- Furnish and install grease trap per Baltimore County requirements and applicable plumbing code
- Domestic hot and cold water piping; angle stops and shutoffs at all fixtures
- Tankless water heaters (2) — AO Smith — furnished and installed with all required connections
- Gas lines rough-in for all gas-fired equipment: pressure fryers (3), open fryers (2), griddles (2), fountain machine, and water heaters
- All plumbing and drain piping concealed; waste piping roughed-in per equipment manufacturer requirements
- Drain piping under lavatories and sinks insulated per ANSI 117.1 Section 606.6
- Splashguard provided between handsink and prep sink; and between prep sink and 3-compartment sink
- All counters and cabinets elevated on 6" legs minimum, open on the business side, on casters or completely sealed to 1/32"

2.10 Electrical

- Complete new electrical service distribution including panel, branch circuits, and all connections per electrical plans
- All wiring: THHN/THWN 600V, ampacities limited to 75°C table values
- All electrical equipment UL-listed and new; all equipment bears UL label per code
- Dedicated circuits provided for all kitchen equipment per manufacturer requirements
- JBOX-HOOD circuit and receptacle for hood control panel; solenoid circuits for gas shut-off under hood
- Flexible conduit final connections at all motors and vibrating equipment
- Exit signs/emergency lighting: combination exit sign/emergency units with 90-min battery backup per Baltimore County code
- Emergency light fixtures with 90-min battery backup at required locations per life safety plan
- All conductors properly grounded; equipment bonded per NEC
- Final inspection: all connections at panelboards, devices, and equipment tested and verified

2.11 Fire Protection & Life Safety

- Kitchen hood fire suppression system coordinated with hood manufacturer and installed per NFPA 96
- All annular spaces at conduit/pipe penetrations through slab and wall sealed with clear silicone per Baltimore County code



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

2.12 Restrooms

- Two (2) restrooms fully built out per ADA requirements: all fixtures, accessories, blocking, tile, and finishes
- ADA-compliant water closets, lavatories, mirrors, grab bars, paper dispensers, and hand dryers/towel holders
- Floor and wall tile with cove base; painted high gloss above 4'-0"
- Exhaust fans vented to exterior per code

2.13 Signage & Accessories

- 3 kiosk stations rough-in and installation per layout (power and data conduit)
- 4 menu screen mounting and blocking per layout
- 60" sneeze guard at counter (60" AFF) per layout
- POS station rough-in
- 55" TV blocking and outlet at dining area per plan
- Trash receptacle enclosure per layout

2.14 Permits & Inspections

- Design Kitchen and Bath to apply for and obtain all required building, electrical, mechanical, and plumbing permits
- Contractor responsible for all required inspections through final Certificate of Occupancy
- All work to comply with applicable IBC, NEC, NFPA, and Baltimore County local codes and ordinances

3. EQUIPMENT SCHEDULE

The following equipment is included in the owner's program. Equipment is to be selected, purchased, and confirmed by the tenant/owner. Contractor to provide all rough-in connections (electrical, plumbing, gas, ventilation) per manufacturer specifications.

Item	Description	Manufacturer	Qty
1	1-Compartment Sink	Regency	1
2	Mop Sink	Eagle Group	1
3	3-Compartment Sink	Regency	1
4	Hand Sink	Stelton	2



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

Item	Description	Manufacturer	Qty
5	Waffle Maker	Carnival King	1
6	Undercounter Refrigerator	Beverage-Air	3
7	Pressure Fryers	Henny Penny (Gas)	3
8	Open Fryers	Henny Penny	2
9	Chef Base	Avantco	1
10	Griddles	Vulcan	2
11	Wire Shelf Units	—	8
12	Undercounter Refrigerator	Avantco	1
13	Warming Stations	Hatco	1
14	Shelving Kits	Stelton	1
15	Strip Warmer	Hatco	2
16	Ice Cream Cabinet	Avantco	1
17	Bun Pan Rack	Regency	1
18	Specialty Warmer	Regency	1
19	Blender	Vitamix Apex	1
20	Refrigerator Car	Avantco	1
21	Ice Maker	Avantco	1
22	Food Warmer	Avantco	1
23	Refrigerated Sandwich/Prep Table	Avantco	1
23A	Heated Cabinet	Hatco GRS-72	1
23B	Double Deck Overshelf	Avantco	1
24	French Fry Warmer	Avantco	1
25	Vertical Toaster	Prince Castle	1
26	Microwave	Solwave	1
27	Glass Door Merchandiser	Tru-Hutch	1
28	Tankless Water Heater	AO Smith	2
29	Fountain Ice Machine	Avantco	1
30	Fountain Machine	Servend	1



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

Note: All equipment must be NSF or ANSI equivalent — ETL Sanitation, UL Classified EPH, CSA Sanitation. Equipment to be selected and confirmed by tenant owner and manufacturer.

4. INCLUSIONS & EXCLUSIONS

Included in This Proposal

- All labor, materials, equipment, tools, and supervision for scopes listed in Section 2
- Building, electrical, mechanical, and plumbing permits and associated fees
- Grease trap furnish and install
- Dumpster rental and debris removal throughout construction
- Final cleaning prior to turnover

Excluded from This Proposal

- Tenant-supplied equipment (owner procurement)
- HVAC rooftop units (provided by Landlord)
- Furniture, fixtures, and décor (tables, chairs, signage graphics)
- Low-voltage data/POS system cabling beyond conduit rough-in
- Structural modifications beyond scope shown on plans
- Any work not specifically listed in Section 2 above
- Permit Fees is not included.

5. PROJECT PRICING

DESCRIPTION	AMOUNT
Complete Tenant Improvement — Nash & Smash Dundalk (2,000 SF)	\$225,000.00
Walk-In Refrigerator, Walk-In Freezer & Hood (Separate Agreement)	\$65,000.00
TOTAL CONTRACT PRICE	\$290,000.00

Note: Walk-in refrigerator, walk-in freezer & hood (\$65,000) is a separate agreement from the base construction contract (\$225,000). Permit fees are not included in the base contract price.



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

Payment Schedule

%	Milestone	Amount Due
30%	Contract Signed (30% of base + Walk-In/Freezer & Hood)	\$132,500.00
15%	Job Start / Mobilization	\$33,750.00
25%	Framing, MEP Inspections Complete	\$56,250.00
15%	Wall Close	\$33,750.00
5%	Equipment Install	\$11,250.00
10%	Final Inspection & Completion	\$22,500.00
100%	TOTAL	\$290,000.00

6. ACCEPTANCE & AUTHORIZATION

By signing below, the Client authorizes Design Kitchen and Bath to proceed with the work described in this proposal under the terms and conditions attached hereto.

Nasrullah Khan

Client Signature

NASRULLAH KHAN

Printed Name & Title

Date

Contractor Signature — Design Kitchen and Bath

Printed Name & Title

Date



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

7. TERMS & CONDITIONS

12.1 Contract Documents

This proposal, together with the approved construction drawings, specifications, and any written change orders, shall constitute the complete agreement between the Owner and Design Kitchen and Bath.

Any modifications to the scope of work must be approved in writing by both parties prior to execution.

12.2 Change Orders

Any additional work requested by the Owner or required due to unforeseen conditions shall be performed only after a written Change Order has been approved.

Change Orders may affect both the project cost and completion time.

12.3 Unforeseen Conditions

This proposal is based on visible conditions and available construction documents at the time of inspection.

Concealed conditions that are not visible during normal inspection may require additional work, including but not limited to:

- Structural issues
- Plumbing deficiencies
- Electrical deficiencies
- Hidden water damage
- Code compliance issues
- Hazardous materials

Such work shall be addressed through an approved change order.

12.4 Owner Supplied Equipment

Equipment supplied by the Owner or third-party vendors is not covered under the contractor's warranty.

Design Kitchen and Bath shall not be responsible for delays, defects, or incompatibility related to owner-supplied equipment.

Additional labor required due to installation complications from owner-supplied equipment may result in additional charges.



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

12.5 Permits and Inspections

Design Kitchen and Bath will coordinate required inspections associated with the construction work.

Permit fees, impact fees, utility company fees, and similar governmental charges are excluded unless specifically stated in the proposal.

12.6 Construction Delays

Design Kitchen and Bath shall not be responsible for delays caused by circumstances beyond its control including but not limited to:

- Permit approval delays
- Utility company delays
- Government inspections
- Weather conditions
- Supply chain disruptions
- Manufacturer delays
- Delays caused by other contractors or vendors

Reasonable time extensions may be required.

12.7 Payment Terms

Payments shall be made in accordance with the payment schedule outlined in this proposal.

Invoices are due within five (5) days of issuance unless otherwise agreed in writing.

Failure to make timely payments may result in suspension of work.

12.8 Right to Stop Work

Design Kitchen and Bath reserves the right to suspend construction activities if payment obligations are not met according to the agreed payment schedule.

Project timelines may be adjusted accordingly.

12.9 Lien Rights

Design Kitchen and Bath reserves the right to file a Mechanic's Lien against the property in accordance with the laws of the State of Maryland in the event of non-payment.

12.10 Warranty



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

Design Kitchen and Bath provides a one (1) year workmanship warranty beginning from the date of project completion.

This warranty does not cover:

- Normal wear and tear
- Improper use or maintenance
- Owner-supplied equipment
- Manufacturer defects covered by manufacturer warranties

12.11 Insurance

Design Kitchen and Bath maintains the following insurance coverage:

- Commercial General Liability Insurance
- Workers Compensation Insurance
- Commercial Auto Insurance

Certificates of insurance can be provided upon request.

12.12 Indemnification

The Owner agrees to indemnify and hold harmless Design Kitchen and Bath from claims arising from owner-supplied materials, equipment, or contractors hired directly by the Owner.

12.13 Governing Law

This agreement shall be governed by and interpreted in accordance with the laws of the State of Maryland.

12.14 Material Price Escalation

This proposal is based on current material pricing at the time of preparation.

If material costs increase due to supply chain disruptions, tariffs, manufacturer price increases, or market fluctuations, Design Kitchen and Bath reserves the right to adjust the contract price accordingly.

Such adjustments will be documented and submitted to the Owner prior to purchase.

12.15 Construction Delays Beyond Contractor Control

Design Kitchen and Bath shall not be responsible for delays caused by circumstances beyond the contractor's reasonable control including:

- Permit delays



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

- Utility company delays
- Weather conditions
- Supply shortages
- Government actions
- Delays by other contractors or vendors

Project schedule adjustments may be required.

12.16 Tenant Financial Responsibility

If the contracting party is a tenant leasing the property, the tenant represents that they have the financial authority to enter into this construction agreement.

In the event of non-payment, Design Kitchen and Bath reserves all legal rights including:

- Suspension of work
- Mechanic's lien filing
- Collection of unpaid balances including legal costs

12.17 Substantial Completion

Substantial Completion shall be defined as the stage at which the project is sufficiently complete for the Owner to occupy or use the premises for its intended purpose.

Minor punch list items shall not delay Substantial Completion.

Final payment obligations shall be triggered upon Substantial Completion.

12.18 Arbitration and Dispute Resolution

In the event of a dispute, the parties shall first attempt to resolve the issue through good faith mediation.

If mediation is unsuccessful, disputes shall be resolved through binding arbitration conducted in the State of Maryland under the rules of the American Arbitration Association (AAA) or a mutually agreed arbitration body.

The decision of the arbitrator shall be final and binding.

12.19 Attorney Fees and Collection Costs

If Design Kitchen and Bath is required to pursue legal action to collect unpaid balances, the Owner agrees to reimburse the contractor for all reasonable collection costs including:

- Attorney fees
- Court costs



8450 Baltimore National Pike Suite 150
Ellicott City, MD 21043
443-653-9941
info@dmv-designandbuild.com
dmv-designandbuild.com

- Arbitration fees
- Collection agency costs

12.20 Kitchen Equipment and Vendor Coordination

Kitchen equipment and specialty food service equipment are typically supplied by the Owner or third-party vendors.

Design Kitchen and Bath will provide standard utility rough-ins and connections as shown on approved drawings but shall not be responsible for:

- Equipment delivery delays
- Vendor installation errors
- Incorrect equipment specifications provided by vendors

Any additional work required due to equipment specification changes shall be treated as a Change Order.